



RECENT PROJECTS

Launch Complex 39B, Kennedy Space Center, FL / Geosyntec Consultants
January 2012 – March 2012

Groundwater sampling up to 75 feet deep utilizing two (2) Geoprobe 6620DT rigs.
Averaged 20 samples per crew, per day

Retail Gas Station, Ocala, FL / ECT
November 2011

Installed 14 Airsparge wells using Sonic method to 98 feet in limestone

Superfund site, Gainesville, FL / Weston Solutions
September 2012 – October 2012

Sonic installation of 2" stainless steel shallow wells, 6" steel surface casing, 2" intermediate wells and rotary installation of 10' steel surface casing – sonic installation of 6" steel secondary casing and 2" stainless steel wells to 150 feet

Superfund site, Tampa, FL / Black & Veatch
September 2012

Sonic installation of 12 injection well clusters with as many as five (5) 1" wells in each boring, also 2" and 4" injection and extraction wells

Vacant site, Wesley Chapel, FL / URS Corp.
November 2010

Installed eight (8) 2" x 250' Monitor wells with 6" x 180' PVC surface casing and temporary 10 1/4" conductor casing, set mud and air rotary

